BRUHAT BANGALORE MAHANAGARA PALIKE

Item No. 71

SCHEDULE - B

Tender Notification No: BBMP/ EE /Btp/Ten/02/2010-11 Dated: 21.01.2011

Name of Work : Improvements of Road and Drain in Kariyanna Palya in Ward No. 7 at Kodigehalli Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of L. Narayanaswamy	
				In Figures	In Words
1	290.25	Removing B.S. Slab Drain and stacking with all lead and lift etc complete as per specifications and directions of engineer in charge of the work.	Sqm	**38.49**	Rupees Thirty Eight and Forty Nine Paise Only
2	50.58	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in **Ordinary soil** not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1 (a) /2.3.5 **(Page No. 5 & Item No. 2.3)**	Cum	**116.64**	Rupees One Hundred Sixteen and Sixty Four Paise Only
3	208.54	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in **Hard Soil** not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1 (a) /2.3.5 **(Page No. 5 & Item No. 2.4)**	Cum	**116.64**	Rupees One Hundred Sixteen and Sixty Four Paise Only
4	290.25	Refixing stone slabs of drains and pointing in CM (1:3) with all lead and lift etc complete as per specifications and directions of engineer in charge of the work.	Sqm	**46.17**	Rupees Forty Six and Seventeen Paise Only
5	56.52	KSRRB 2900-4.1: Providing and laying in position **plain cement concrete mix 1:4:8** with stone aggregate 40mm and down size in foundation upto a depth of 2m below ground level and upto a height of 1.5m above ground level / bed level machine mixed, concrete laid in layers not exceeding 15cms thick well compacted, cost of all materials, labour, HOM of machineries, curing complete as per specifications. **(Page.12 & Item No. 4.3)**	Cum	**3014.17**	Rupees Three Thousand Fourteen and Seventeen Paise Only
6	61.44	KSRB 4-1.5 : Providing and laying in position **plain cement concrete** of mix **1:1.5:3** using 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 **(Page No. 12 & Item No. 4.11).**	Cum	**4349.70**	Rupees Four Thousand Three Hundred Forty Nine and Seventy Paise Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of L. Narayanaswamy	
				In Figures	In Words
7	15.11	KSRB 5.2-3 : Providing and constructing granite / trap / basalt **size stone masonry** in foundation cement mortar **1:6,** stone hammered dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specification. KBS 5.1.13 **(Page : 22 Item No. 5.6)**	Cum	**2286.26**	Rupees Two Thousand Two Hundred Eighty Six and Twenty Six Paise Only
8	9.36	KSRB 4.2.2 : Providing and laying in position **reinforced cement concrete** of mix **1:1.5:3** with 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.6. **(Page No. 12 & Item No. 4.11)**	Cum	**4411.91**	Rupees Four Thousand Four Hundred Eleven and Ninety One Paise Only
9	11.23	KSRB 4.9.2 : Providing **T.M.T. Steel reinforcement for R.C.C.** work including straightening, cutting, bending, hooking , placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3. **(Page No. 16 & Item No. 4.46)**	Sqm	**4684.07**	Rupees Four Thousand Six Hundred Eighty Four and Seven Paise Only
10	33.20	KSRB 2900-8.1 : Providing flush pointing to stone masonry with cement mortar 1:3, 20mm deep raking joints to depth of 25mm, nicely lining, including cost of all labour, curing complete as per specifications. Specification No. KRBS 1000, 1300 MOST Specification No. 1000 / 1300 **(Page No. 97 & Item No. 15.1).**	Sqm	**59.78**	Rupees Fifty Nine and Seventy Eight Paise Only
11	101.85	KSRRB M300-53 : Construction of embankment with approved material Gravel/Murrum with all lifts and leads, trasnporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) MORTH Specification No. 305. **(Page No. 133 & Item No. 19.60)**	Cum	**132.19**	Rupees One Hundred Thirty Two and Nineteen Paise Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of L. Narayanaswamy	
				In Figures	In Words
12	101.85	KSRB M400-7 : Consturction of granular sub-base by providing Coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per specifications. FOR GRADING III Material. **(Page No. 141 & Item No. 20.6.3)**	Cum	**742.61**	Rupees Seven Hundred Forty Two and Sixty One Paise Only
13	19.08	KSRB 4-6.2: Providing and removing centering, shuttering, strutting, propping, etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes thickness above 200mm including cost of all materials, labour complete as per specifications.(P14/4.30)	Sqm	**179.82**	Rupees One Hundred Seventy Nine and Eighty Two Paise Only
14	55.48	**Lead for disposal** of debris shall be payable at Carriage rates by mechanical means including loading and unloading - 0.00 to 2.00 Kms as per the directions of the Engineer in charge of the work	Cum	**60.59**	Rupees Sixty and Fifty Nine Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92